

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains 79.70	<p>$\frac{1}{4}$ sec. cor. between secs. 3 and 4. Land, level. Soil, good. Very little grass.</p>
79.85	<p>East on random through N.$\frac{1}{2}$ of sec. 3. Var. 21° East. Commencing at 1/16 sec. cor., 20 chains N. of $\frac{1}{4}$ sec. cor. between secs. 3 and 4 and set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at Intersect E. bdy., 50 lks. N. of 1/16 sec. cor. between secs. 2 and 3. Thence North 89°39'W. on true line. Var. 20° East.</p>
19.96	<p>Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5$\frac{1}{2}$ ft. dist., raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
39.93	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5$\frac{1}{2}$ ft. dist., raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
59.89	<p>Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5$\frac{1}{2}$ ft. dist., raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
79.85	<p>1/16 sec. cor. between secs. 3 and 4. Land, level. Soil, 1st rate. Grass, poor.</p>
	<p>East on random through S.$\frac{1}{2}$ of sec. 9. Commencing at 1/16 sec. cor., 20 chains N. of S.W. cor. of sec. 9. Var. 20° East.</p>