

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	<p>5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
30.50	Dry ditch, course N.W.
39.95	<p>Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
50.25	Wagon road, N. and S.
59.92	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in ground marked 1/16 S on N. face.</p>
79.90	<p>1/16 sec. cor. between secs. 8 and 9. Land, level. Soil, 1st rate. Grass, fair. October 29, 1887.</p>
	<p>East on random through S. ½ of sec. 4. Commencing at 1/16 sec. cor., 20 chains N. of S.W. cor. of sec. 4. Var. 20½° East. Set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at</p>
80.00	<p>Intersect E. bdy., 42 lks. N. of 1/16 sec. cor. between secs. 3 and 4. Thence N.89°42'W. on true line. Var. same.</p>
18.25	Enter field, N. and S.
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft.</p>