

## Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
59.94	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.92	1/16 sec. cor. between secs. 4 and 5. Land, level. Soil, 1st rate and almost barren of grass &c.
East on random through S. ½ of sec. 8. Var. 21½° East.	
Commencing at 1/16 sec. cor., 20 chains N. of S.W. cor. to sec. 8.	
Set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at	
80.00	Intersect E. bdy, 30 lks. N. of 1/16 sec. cor. between secs. 8 and 9. Thence N.89°47'W. on true line. Var. same.
20.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of cor., 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake,