

## Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	<p>East on random through S. <math>\frac{1}{2}</math> of sec. 5.  Var. 20° East.</p> <p>Commencing at 1/16 sec. cor., 20 chains N. of S.W. cor. of sec. 5.</p> <p>Set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at .</p> <p>79.92 Intersect E. bdy., 35 lks. N. of 1/16 sec. cor. between secs. 4 and 5. Thence  N. 89° 45' W. on true line.  Var. same.</p> <p>19.98 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5 <math>\frac{1}{2}</math> ft. dist., raised mound of earth 1 <math>\frac{1}{2}</math> ft. high, 3 <math>\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p> <p>39.96 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5 <math>\frac{1}{2}</math> ft. dist., raised mound of earth 1 <math>\frac{1}{2}</math> ft. high, 3 <math>\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p> <p>59.94 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5 <math>\frac{1}{2}</math> ft. dist., raised mound of earth 1 <math>\frac{1}{2}</math> ft. high, 3 <math>\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p> <p>79.92 1/16 sec. cor. between secs. 5 and 6.  Land, level.  Soil, 1st rate. Not cultivated.  Some grass and weeds.</p>	
	<p>East on random through center of sec. 5.  Var. 20° East.</p> <p>Commencing at <math>\frac{1}{4}</math> sec. cor. between secs. 5 and 6, set temporary <math>\frac{1}{4}</math> and 1/16 sec. cors. at 20, 40 and 60</p>	