

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	
79.90	<p>chains and at</p> <p>Intersect E. bdy., 30 lks. N. of $\frac{1}{4}$ sec. cor. between secs. 4 and 5. Thence</p> <p>N.89°47'W. on true line.</p> <p>Var. same.</p>
19.98	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
39.95	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on N. face.</p>
59.93	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
79.90	<p>$\frac{1}{4}$ sec. cor. between secs. 5 and 6.</p> <p>Land, level.</p> <p>Soil, 1st rate. Grass short.</p>
	<p>East on random through N.$\frac{1}{2}$ of sec. 5.</p> <p>Var. 20° East.</p> <p>Commencing at 1/16 sec. cor., 20 chains N. of $\frac{1}{4}$ sec. cor. between secs. 5 and 6.</p> <p>Set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at</p>
80.00	<p>Intersect E. bdy., 35 lks. N. of 1/16 sec. cor., 20 chains N. of $\frac{1}{4}$ sec. cor. between secs. 4 and 5. Thence</p> <p>N.89°45'W. on true line.</p> <p>Var. same.</p>