

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	<p>on E. bdy. sec. 12, T. 1 N., R. 33 E. and set basalt stone, 12x10x10 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. closing cor. marked $\frac{1}{4}$ C C on E. face. Dug pits, 18x18x12 ins., E. N. and S. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>Land, rolling.</p> <p>Soil, 1st rate. Very little grass.</p>
	<p>West on true line through N. $\frac{1}{2}$ of sec. 7.</p> <p style="text-align: center;">Var. $20\frac{1}{2}^{\circ}$ East.</p>
	<p>Commencing at 1/16 sec. cor., 20 chains N. of $\frac{1}{4}$ sec. cor. between secs. 7 and 8.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
40.50	<p>Dry ditch, course N.W.</p>
54.00	<p>Dry galch, course N.W.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>
77.42	<p>Intersect W. bdy. Township, 16.80 chs., S. of cor. to secs. 1 and 12, T. 1 N., R. 32 E. and set basalt stone, 10x10x10 ins., 7 ins. in the ground for closing 1/16 sec. cor. marked 1/16 C C on E. face. Dug pits, 18x18x12 ins., N. E and S of stone, $5\frac{1}{2}$ ft. dist., raised</p>