

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains

mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.

Land, rolling.

Soil, 1st rate.

Grass &c grazed off closely.

October 31, 1887.

West through S. $\frac{1}{2}$ of sec. 6.Var. 20° East.Commencing at $1/16$ sec. cor., 20 chains N. of S.E. cor.
to sec. 6.

- 20.00 Set basalt stone, 10x8x6 ins., 7 ins. in the ground for
 $1/16$ sec. cor. marked $1/16$ on N. face. Dug pits,
18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised
mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
- 40.00 Set basalt stone, 9x9x8 ins., 6 ins. in the ground, for
 $1/16$ sec. cor. marked $1/16$ on N. face. Dug pits,
18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised
mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
- 60.00 Set basalt stone, 10x8x7 ins., 7 ins. in the ground marked
 $1/16$ on N. face for $1/16$ sec. cor. Dug pits, 18x18x12
ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised
mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and
piled up mound of rock alongside.
- 61.00 Wagon road, course S.W.
- 65.55 Dry bed of creek, course N.
- 77.25 Intersect W. bdy. of Township, 16.85 chains S. of $\frac{1}{4}$ sec.
cor. on E. bdy. sec. 1, T. 1 N., R. 32 E. and set
basalt stone, 10x10x8 ins., 7 ins. in the ground for
 $1/16$ sec. closing cor. marked $1/16$ C C on E. face. Dug
pits, 18x18x12 ins. N. E. and S. of stone, $5\frac{1}{2}$ ft. dist.,
raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.

Land, mostly level.

Soil, 1st rate generally. Not much grass.

West on true line through center of sec. 6.

Var. 20° East.