

## Sub-Subdivisions of T. 1 N., R. 33 E.

Chains 20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on N. face.
40.40	Wagon road, North.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
77.15	Intersect W. bdy. Township, 315 lks. N. of ¼ sec. cor. to E. bdy. S 1, T. 1 N., R. 32 E. and set stone, 12x10x10 ins., 8 ins. in the ground for ¼ sec. closing cor. marked ¼ C C on E. face. Dug pits, 18x18x12 ins., E. S. and N. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it. Land, mostly level. Soil, 1st rate. Not cultivated. Very little grass.
	West on true line through N. ½ of sec. 6. Var. 20° East.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.