

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 11
39.96	Set basalt stone, 10x9x8 ins., 7 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face, and raised mound of stone on bed of rock. Pits impracticable.
42.50	Tudie Willow Creek, course N.W., water in holes
59.95	Intersect the N. and S. line between secs. 10 and 11 at 1/16 sec. cor.
	Land, mountainous and rolling.
	Soil, mostly 1st rate, some rocky.
	Good grass.
	From the 1/16 sec. corner, 20 chs. S. of the 1/4 sec. corner between secs. 2 and 11. I run South on true line in sec. 11.
	Var. 15° E.
4.00	Low summit, course S.W.
10.00	Set a basalt stone, 14x10x5 ins., 10 ins. in the ground, for 1/32 sec. corner marked 1/32 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, and 3 1/2 ft. base over it.
	Descend.
20.00	Set a basalt stone, 16x9x7 ins., 12 ins. in the ground, for 1/4 sec. corner marked 1/4 on W. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.
	Line over a summit.
	Soil, 1st rate.
	Grass and weeds.
	East on true line in sec. 11.
	Var. 19° East.
	Leave bottom.
	Along side hill.
10.00	Set basalt stone, 12x12x5 ins., on a ledge of rock, and