

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains 10.00	<p style="text-align: center;">Sec. 11</p> <p>Set stone, 12x12x5 ins., 8 ins. in the ground, for 1/32 sec. corner marked 1/32 on W. face. Dug pits, 18x18x12 ins., N. and S. of corner, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Weeds.</p>
20.00	<p>From the ½ sec. corner between secs. 11 and 14, which is a basalt stone, 18x10x10 ins., 12 ins. in the ground, marked ¼ on N. face and mound of stone over it.</p> <p>I run</p> <p>North on true line in sec. 11.</p> <p style="text-align: center;">Var. 19° E.</p> <p>Set a basalt stone, 10x8x7 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. and 1/32 on E. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Grass and weeds.</p>
10.00	<p>East on true line in sec. 11.</p> <p style="text-align: center;">Var. 20° East.</p> <p>Along side hill.</p> <p>Tudie Willow Creek on N.</p> <p>Set a basalt stone, 12x7x5 ins., 8 ins. in the ground, for 1/32 sec. corner, marked 1/32 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p>This corner is situated South of Tudie Willow Creek, 350 lks., course N.W.</p> <p>Land, mountainous and steep.</p> <p>Soil, 1st rate and rocky. Grass.</p> <p>Timber, some cottonwood along creek.</p>