

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 11
	<p>From the 1/16 sec. corner, 20 chs. N. of the corner to secs. 10, 11, 14 and 15, which is a charred stake, and pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., mound of earth 1½ ft. high and 3½ ft. base over it. In N. pit a stake 2 ins. square marked 1/16 S on W. face.</p> <p>I run N.89°51'E. on random line in sec. 11. Var. 19°E.</p>
20.00	Set temp. 1/16 sec. corner.
40.06	Intersect the East line through the center of sec. 11, 6 lks. S. of 1/16 sec. corner.
	<p>Thence I run S.89°46'W. on true line in sec. 11. Var. 20° E.</p>
17.00	Gulch.
20.03	Set a basalt stone, 10x10x5 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.
30.00	Gulch, course N. <span style="float: right;">-50</span>
40.06	To 1/16 sec. corner, 20 chs. N. of the corner to secs. 10, 11, 14 and 15.
	<p>Land, mountainous. Soil, 1st rate. Good grass.</p>
	<p>From the corner to secs. 10, 11, 14 and 15, which is basalt stone, 10x10x8 ins., 7 ins. in the ground, marked 4 notches on S. and 2 notches on E. edges, with pits, 18x18x12 ins., in each section, 5½ ft. dist., and mound of earth 2 ft. high, 4½ ft. base over it. I erased the Letters D R on the corner stone.</p> <p>I run N.89°51'E. on random line between secs. 11 and 14. Var. 22°E.</p>
20.00	Set temporary 1/16 sec. cor.