

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains 39.95	Intersect the $\frac{1}{4}$ sec. cor., which is a basalt stone, 18x10x10 ins., 12 ins. in the ground, marked $\frac{1}{4}$ on N. face and mound of stone over it. Thence I run S.89°51'W. on true line between secs. 11 and 14. Var. 20°30'E.
19.97	Set basalt stone, 10x10x6 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face and raised a mound of stone over it. Pits impracticable.
22.20	Summit, course N. Descend.
39.95	To the corner to secs. 10, 11, 14 and 15. Land, rolling. Soil, 1st rate. Good grass.

+40

Sec. 15

From the 1/16 sec. corner, 19.88 chains W. of the corner,
to secs. 10, 11, 14 and 15, which is a stake with pits,
18x18x12 ins., E. and W., $5\frac{1}{2}$ ft. dist., and mound of
earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In E. pit, a
stake, 2 ins. square, marked 1/16 S on N. face.

Thence I run
South on true line in section 15.

Var. 20° 30'E.

12.60	Tudie Willow Creek, course N.W., water in holes.
20.00	Set basalt stone, 12x9x6 ins., 8 ins. in the ground, for 1/16 sec. corner, marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Land, mountainous. Soil, rich. Good grass.

From the corner to secs. 15 and 16, 21 and 22, which is
a basalt stone, 9x8x8 ins., 6 ins. in the ground, marked ✓