

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 15
20.00	Set temporary $\frac{1}{4}$ sec. cor.
39.85	Intersect the N. and S. line at $\frac{1}{4}$ sec. corner between secs. 15 and 16. Thence I run S. $89^{\circ}46'E.$ on true line in sec. 15. Var. $20^{\circ}E.$
12.50	Trail, course N.W.
19.92	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
39.85	To the $\frac{1}{4}$ sec. corner at center of sec. 15. Land, the 1st 20 chains level, balance point of hill. Soil, 1st rate. Grass.
	From the $\frac{1}{4}$ section corner in the center of sec. 15. I run South on true line in sec. 15. Var. $20^{\circ}E.$
4.00	Summit, course W.
12.00	Creek, course N.W., little water.
20.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner, marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
	Thence I run East on true line in sec. 15. Var. $21^{\circ}E.$
13.50	Creek, course N.W.
20.00	Set basalt stone, 14x9x8 ins., 10 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.