

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 15
	Land, rolling and mountainous. Soil, 1st rate. Grass and weeds.
	From the 1/16 sec. corner, 20 chs. South of 1/4 sec. corner in the center of secs. 15. I run N.89°40'West on true line in sec. 15. Var. 19°15'East.
20.00	Set stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.
24.50	Gulch and ditch, course N.W.
31.00	Road, course N.
40.00	To the 1/16 sec. corner between secs. 15 and 16. Land, rolling. Soil, 1st rate. Grass and weeds.
	From the corner to secs. 15 and 16, 21 and 22. I run S.89°39'East on true line between secs. 15 and 22. Var. 20°E.
19.91	Set a basalt stone, 13x9x7 ins., 9 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.
39.82	Intersect the old 1/4 sec. corner, which is a charred stake with pits E. and W. of stake, 5 1/2 ft. dist., and mound of earth over it. In E. pit, stake 12 ins. above ground, 2 ins. square, marked 1/4 S on N. face. Along mountainside.
59.73	Set a basalt stone, 10x7x6 ins., 7 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face. Dug