

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	<p style="text-align: center;">Sec. 15</p> <p>pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>79.65 The corner to secs. 14, 15, 22 and 23, which is a post, 4 ins. square, marked T 1 N S 14 on N.E., R 33 E S 23 on S.E., S 22 on S.W. and S 15 on N.W. faces with 3 notches on S. and 2 notches on E. edges, with pits, 18x18x12, in each sec., $5\frac{1}{2}$ ft. dist., and mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base around post.</p> <p>Land, mountainous and smooth.</p> <p>Soil, 1st rate.</p> <p>Good grass.</p>
	<p style="text-align: center;">Sec. 16</p> <p>From the corner to secs. 16, 17, 20 and 21, which is a basalt stone, 9x8x7 ins., 6 ins. in the ground, marked with 3 notches on S. and 4 notches on E. edges, with pits, 18x18x12 ins., in each sec., $5\frac{1}{2}$ ft. dist., and mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.</p> <p>Thence I run</p> <p>S.89°45'E. on true line between secs. 16 and 21.</p> <p style="text-align: center;">Var. 20°E.</p> <p>3.50 Ditch, course N.W.</p> <p>20.00 Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{16}$ sec. corner, marked $\frac{1}{16}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>30.00 Road, course N. and S.</p> <p>40.00 The old $\frac{1}{4}$ sec. corner, which is a basalt stone, 9x8x7 ins., 6 ins. in the ground marked $\frac{1}{4}$ on N. face, with pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>60.00 Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{16}$ sec. corner marked $\frac{1}{16}$ on N. face, and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>