

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 16 Setting temporary 1/16 and $\frac{1}{4}$ corners at 20, 40 and 60 chains and at
80.00	Intersect the E. bdy., 12 lks. S. of the $\frac{1}{4}$ sec. corner, between secs. 15 and 16. Thence I run N.89°49'W. on true line through the center of sec. 16. Var. 19°30'E.
20.00	Deposited a marked stone, 12 ins. in the ground, for 1/16 sec. corner. Dug pits, 18x18x12 ins., E. and W. of corner, 5 $\frac{1}{2}$ ft. dist. and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
28.00	Gulch, course N.W.
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. corner marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
48.00	Road, course N.
60.00	Set a basalt stone, 9x7x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
80.00	To the $\frac{1}{4}$ sec. corner between secs. 16 and 17. Land, mostly level. Soil, 1st rate. Grass weeds and wild alfalfa.
	From the 1/16 sec. corner, 20 chains N. of the $\frac{1}{4}$ sec. cor. between secs. 16 and 17. I run S.89°43'E. on a random line through the N. $\frac{1}{2}$ of sec. 16. Var. 21° E. Setting temporary 1/16 sec. corners at 20, 40 and 60 chains and at