

Subdivisions and Allotments of T. 1 N., R. 33 E.

| | |
|--------|---|
| Chains | Sec. 16 |
| 80.00 | Intersect the East bdy. of sec. 16, 10 lks. N. of the 1/16 sec. corner between secs. 15 and 16. |
| | Thence I run |
| | N. 89° 39' W. on true line through the N. $\frac{1}{8}$ of sec. 16. Var. 20° E. |
| 20.00 | Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it. |
| 40.00 | Set stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it. |
| 48.00 | Road, course N. and S. |
| 54.40 | Dry bed of creek, course N.W. |
| 60.00 | Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it. |
| 80.00 | To the 1/16 sec. corner between secs. 16 and 17. Land, rolling. Soil, 1st rate. Grass and weeds. |
| | June 18, 1889. |
| | Sec. 17 |
| | From the corner to secs. 17, 18, 19 and 20, which is a basalt stone, 12x10x8 ins., 8 ins. in the ground, marked with 3 notches on S. and 5 notches on E. edges, with pits, 18x18x12 ins., in each sec., 5 $\frac{1}{2}$ ft. dist., and mound of earth 2 ft. high, 4 $\frac{1}{2}$ ft. base over it. |
| | Thence I run |
| | East on random line between secs. 17 and 20. Var. 20° E. |
| | Setting temporary 1/16 section corners at 20 and 60 chains at 39.90 chains I pass the $\frac{1}{2}$ sec. corner, 6 lks. South, and at |