

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 17
79.80	Intersect N. and S. line, 12 lks. S. of corner to secs. 16, 17, 20 and 21. Thence I run S.89°55'W. on true line between secs. 17 and 20. Var. 23°East.
13.95	Trail, course N.
19.95	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it.
35.25	Trail, course N.
39.90	The old ¼ sec. corner, which is a stone, 12x8x8 ins., 8 ins. in the ground, marked ¼ on N. face. Pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., mound of earth 1½ ft. high, 3½ ft. base over it.
59.85	Set a basalt stone, 11x8x6 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.
64.00	Gulch, course N.W.
79.80	The corner to secs. 17, 18, 19 and 20. Land, mostly level. Soil, 1st rate. Good grass.
	North between secs. 17 and 18. Var. 20°30'E.
20.00	Set basalt stone, 10x8x5 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high and 3½ ft. base over it.
23.25	(Omitted).
40.00	To the old ¼ sec. corner, which is a basalt stone, 14x9x7 ins., 10 ins. in the ground, marked ¼ on W. face, and a mound of stone over it.