

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 18
	From the $\frac{1}{4}$ sec. corner between secs. 18 and 19.
	I run
	North on true line in sec. 18
	Var. 20°E.
1.00	Trail, course N.W.
2.50	Gulch, course N.W.
4.00	Ascend bank.
4.50	Top of bluff or bank.
20.00	Deposited marked stone, 12 ins. in the ground, for 1/16 sec. corner. Dug pits, 18x18x12 ins., N. and S. of corner, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on W. face.
	Land, mostly level.
	Soil, ashy.
	Grass and weeds.
	From the 1/16 sec. corner, 20 chs. North of cor. to secs. 17, 18, 19 and 20.
	I run
	West on random line in sec. 18.
	Var. 20°E.
	Setting temporary 1/16 sec. cor. at 20 chs., and at
40.00	Intersect line at 1/16 sec. corner, 20 chains N. of $\frac{1}{4}$ sec. cor. between secs. 18 and 19.
	Thence I run
	East on true line in sec. 18.
	Var. 20°E.
4.00	Trail, course N.W.
20.00	Deposited a marked stone, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of corner, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.

+20