

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains 40.00	<p style="text-align: center;">Sec. 18</p> <p>To the 1/16 sec. corner, 20 chains N. of corner to secs. 17, 18, 19 and 20.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p> <p>Weeds.</p>
78.50	<p>From the <math>\frac{1}{4}</math> sec. corner between secs. 17 and 18.</p> <p>I run</p> <p>West on random line through the center of sec. 18.</p> <p style="text-align: center;">Var. 20° E.</p> <p>Setting temporary corners at 20, 40 and 60 chains, and at</p> <p>Intersect the N. and S. line on West bdy. of Tp., 6 lks.</p> <p style="text-align: center;">S. of <math>\frac{1}{4}</math> sec. corner on West bdy. of sec. 18.</p> <p>Thence I run</p> <p>S.89°57'E. on true line through the center of sec. 18.</p> <p style="text-align: center;">Var. 20° E.</p>
18.50	<p>Deposited marked stone, 12 ins. in the ground, for 1/16 sec. corner. Dug pits, 18x18x12 ins., E. and W. of corner, <math>5\frac{1}{2}</math> ft. dist., raised a mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it. In E. pits drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
34.60	<p>Road, course N.W.</p>
38.50	<p>Set stone, 9x8x7 ins., 6 ins. in the ground, for <math>\frac{1}{4}</math> sec. corner marked <math>\frac{1}{4}</math> on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, <math>5\frac{1}{2}</math> ft. dist., and raised a mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it.</p>
58.50	<p>Set stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, <math>5\frac{1}{2}</math> ft. dist., and raised a mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it.</p>
78.50	<p>To the <math>\frac{1}{4}</math> sec. corner between secs. 17 and 18.</p> <p>Land, level.</p> <p>Soil, 2nd and 3rd rate.</p> <p>Very little vegetation.</p>