

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 18
	From the 1/16 sec. corner, 18.50 chains E. of $\frac{1}{4}$ sec. corner on West bdy. of sec. 18.
	I run
	North on true line in sec. 18.
	Var. 20°E.
20.00	Set stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner, marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
	Land, level.
	Soil, 2nd and 3rd rate.
	Very little vegetation.
	From the 1/16 sec. corner, 20 chs. N. of $\frac{1}{4}$ sec. corner between secs. 17 and 18.
	I run
	West on random line through the N. $\frac{1}{2}$ of sec. 18.
	Var. 19°15'East.
	Setting temporary corner at 20 and 40 chains and at
60.00	Intersect the N. and S. line, 5 lks. N. of 1/16 sec. corner, 18.50 chains E., and 20 chs. N. of $\frac{1}{4}$ sec. corner on W. bdy. of sec. 18.
	Thence I run
	N.89°57'E. on true line through the N. $\frac{1}{2}$ of sec. 18.
	Var. 20°E.
20.00	Deposited marked stone, 12 ins. in the ground, for 1/16 sec. corner. Dug pits, 18x18x12 ins., E. and W. of corner, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
24.50	Road, course N.W.
40.00	Set stone, 10x8x7 ins., 7 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.