

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains 46.50	Sec. 18 Bed of creek, course N.W.
60.00	The 1/16 sec. corner, 20 chs. N. of $\frac{1}{4}$ sec. corner between secs. 17 and 18. Land, mostly level. Soil, good. Grass and weeds.
20.00	<p style="text-align: center;">Sec. 19</p> <p>From the corner to secs. 19, 20, 29 and 30, which is a basalt stone, 16x10x6 ins., 10 ins. in the ground, marked with 2 notches on S. and 5 notches on the E. edges, with pits, 18x18x12 ins., in each sec., $5\frac{1}{2}$ ft. dist., and mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.</p> <p>Thence I run West on true line between secs. 19 and 30.</p> <p style="text-align: center;">Var. $20\frac{1}{2}^{\circ}$ E.</p> <p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>
40.00	<p>The old $\frac{1}{4}$ sec. corner, which is a basalt stone, 10x8x8 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on N. face. Pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>Land, mostly level. Soil, 2nd and 3rd rate. Weeds.</p>
1.72	<p>From the corner to secs. 18 and 19 on W. bdy. of Tp. I run South.</p> <p style="text-align: center;">Var. 21° E.</p> <p>Pass corner to secs. 13 and 24, T. 1 N., R. 32 E., which is a basalt stone, 9x8x7 ins., 6 ins. in the ground, marked with 3 notches on N. and S. edges. Pits,</p>