

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 19
	<p>Land, rolling. Soil, 3rd rate. Very little grass.</p>
	<p>Sec. 20</p>
	<p>From the corner to secs. 20, 21, 28 and 29, which is a basalt stone, 12x12x12 ins., 8 ins. in the ground, marked with 2 notches on S. and 4 notches on E. edges. Pits, 18x18x12 ins., in each sec., 5½ ft. dist., and mound of earth 2 ft. high, 4½ ft. base over it.</p>
	<p>I run S.89° 55'W. on true line between secs. 20 and 29. Var. 20°30'East.</p>
20.00	<p>Dry ditch, course N.W. Set basalt stone, 10x8x7 ins., 7 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face, and raised mound of stone alongside. Pits impracticable. Corners set on N. bank.</p>
40.00	<p>To the old ¼ sec. corner, which is a basalt stone, 12x12x10 ins., 8 ins. in the ground, marked ¼ on N. face. Pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and mound of earth 1½ ft. high, 3½ ft. base over it.</p>
60.00	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face; and dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.</p>
80.00	<p>The corner to secs. 19 and 20, 29 and 30. Land, level. Soil, ashy. Weeds.</p>
	<p>From corner to secs. 20, 21, 28 and 29. I run North on true line between secs. 20 and 21. Var. 20°30'East.</p>