

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 21
79.80	<p>To the corner of secs. 21, 22, 27 and 28, on the summit, which is a basalt stone, 18x18x12 ins., 12 ins in the ground, marked with 2 notches on S. and 3 notches on E., and mound of stone over it.</p> <p>Land, rolling and mountainous.</p> <p>Soil, 1st rate.</p> <p>Good grass.</p>
North between secs. 21 and 22.	
Var. 20° E.	
20.00	<p>Set basalt stone, 12x12x7 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face and raised a mound of stone over it, on the bank of creek. Pits impracticable.</p>
23.00	Canyon, course W.
40.00	<p>To the $\frac{1}{4}$ sec. corner, which is a basalt stone, 9x8x7 ins., 6 ins. in the ground marked $\frac{1}{4}$ on W. face. Pits, 18x18x12 ins., N. and S. of stone, 5$\frac{1}{2}$ ft. dist., and mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it.</p>
60.00	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5$\frac{1}{2}$ ft. dist., and raised a mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it.</p>
73.50	Gulch, course W.
80.00	<p>To the corner to secs. 15, 16, 21 and 22.</p> <p>Land, rolling.</p> <p>Soil, 1st and 2nd rate.</p> <p>Good grass.</p>
<p>From the 1/16 sec. corner, 20 chs. N. of corner to secs. 20, 21, 28 and 29.</p>	
I run	
S.89°40'E. on random line through section 21.	
Var. 20° E.	