

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 21
	N.89°39'W. on true line through N. $\frac{1}{2}$ of sec. 21. Var. 21°E.
13.00	Road, course N. and S.
20.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
41.00	Gulch, course N.W.
54.25	Road, course N. and S.
60.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
80.00	To the 1/16 sec. corner, 20 chs. N. of $\frac{1}{4}$ sec. cor. between secs. 20 and 21. Land, rolling. Soil, 2nd rate. Good grass.
	Sec. 22
	From the 1/16 sec. corner, 19.94 chains E. of the corner to secs. 15, 16, 21 and 22. I run South on true line in sec. 22. Var. 21°E.
17.00	Gulch, course W.
20.00	Set basalt stone, 10x7x7 ins., 6 ins., in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.