

Base Line of T. 1 N., R. 33 E.

Chains	East on South boundary of sec. 34. Var. 21°45'E.
40.00	Set qr. sec. post in mound of earth, drove charred stake as per instructions. Here reach top of undulating mountain table land of good soil producing fine bunch grass. Yarrow, sunflower and wild rose bush. Small groves of scattering pine.
80.00	Set post corner to secs. 34 and 35 on the edge of bluff, made mound of earth and drove charred stake as per instructions. Var. 16°30'E.
	East on South boundary of sec. 35. Var. 16°30'E.
18.00	Bottom of ravine.
25.75	Commence to ascend.
40.00	Set qr. sec. post, made mound of rock on edge of table land. Var. 22°45'E.
80.00	Set post corner to secs. 35 and 36 on the side of ridge dipping to the North. Made mound of earth and drove charred stake as per instructions. Var. 26°E.
	Timber in the Hollows; but no water.
	Thence East on South boundary of sec. 36. Var. 26°E.
35.50	Bottom of ravine. North fork of McKays Creek, 25 lks. wide, water in pools runs N.W. Timber along creek consists of pine, fir, alder, cottonwood and cherry.
40.00	Set qr. sec. post, made mound of earth, drove charred stake as per instructions.
80.00	Set post corner to secs. 31 and 36, Townships 1 North, Ranges 34 and 35 East, made mound of earth, drove charred stake as per instructions. Var. 20°East.