

Exteriors of T. 1 N., R. 34 E.  
 Surveyed by Zenas F. Moody under contract No. 145.  
 Dated April, 23, 1871.

East Boundary

Chains	
40.00	Begin at the South East corner to Township 1 N., Range 34 East on Base Line. I run North on East boundary of sec. 36. Var. 21°E. Set basalt stone, 18x14x12, for $\frac{1}{4}$ sec. corner.
63.00	McKay creek, 14 lks. wide, flows West.
80.00	Set basalt stone, 16x14x14, for corner to sections 25, 36, 30 and 31. Land, mountainous. Soil, 2nd rate. Some grass. Good pine and fir timber.
40.00	North on East boundary sec. 25. Var. 20°E. Set post for $\frac{1}{4}$ sec. corner from which A pine, 36 ins. diam., bears N.82°E.
80.00	Set basalt stone, 14x14x12, for corner to secs. 24, 25, 19 and 30. Land, mountainous. Soil, 2nd rate. Some grass. Pine timber.
20.00	North on East boundary sec. 24. Var. 20°30'E. Brook, 5 lks. wide, flows E.
40.00	Set post and raised stone mound for $\frac{1}{4}$ sec. corner.
46.75	Brook, 8 lks. wide, flows East.
80.00	Set basalt stone, 18x14x12, for corner to sections 13, 24, 18 and 19. Land, mountainous. Soil, 2nd rate. Grass, good. Pine and fir timber.
	May 6, 1871.
	North on East boundary of sec. 13. Var. 20°30'E.