

North Boundary of T. 1 N., R. 34 E.

Chains	
<p>38.50</p> <p>78.50</p>	<p>West on random line on North boundaries of secs. 1, 2, 3, 4, 5, 6, 7.</p> <p style="text-align: center;">Var. 20°E.</p> <p>I set temporary half mile and mile posts at every 40 and 80 chains and at 5 miles, 78 chains and 50 links to a point 2 chains North of the corner of Townships 1 and 2 N., R. 33 and 34 East.</p> <p>N.89°46' East on true line on North boundary of sec. 6.</p> <p>Set basalt stone, 14x12x8, for $\frac{1}{4}$ sec. corner.</p> <p>Set basalt stone, 18x14x12, for corner to secs. 5, 6, 31 and 32.</p> <p>Land, hilly.</p> <p>Soil, 1st rate. Good grass.</p>
<p>40.00</p> <p>54.00</p> <p>80.00</p>	<p>North 89°46' East on North boundary of sec. 5 .</p> <p style="text-align: center;">Var. 21° E.</p> <p>Set basalt stone, 14x12x8, for $\frac{1}{4}$ section corner.</p> <p>Brook, 4 lks. wide, flows N.</p> <p>Set basalt stone, 16x14x10, for corner to secs. 4, 5, 32 and 33.</p> <p>Land, hilly.</p> <p>Soil, 1st rate. Good grass.</p>
<p>40.00</p> <p>76.00</p> <p>80.00</p>	<p>North 89°46' East on North boundary sec. 4.</p> <p style="text-align: center;">Var. 21° East.</p> <p>Set basalt stone, 14x12x10, for $\frac{1}{4}$ sec. corner.</p> <p>Brook, 5 lks., flows N.</p> <p>Set basalt stone, 14x14x14, for corner to secs. 3, 4, 33 and 34.</p> <p>Land, hilly.</p> <p>Soil, 1st rate. Good grass.</p>
	<p>North 89°46' East on true line on North boundary of sec. 3.</p> <p style="text-align: center;">Var. 21° East.</p>