

## Subdivisions of T. 1 N., R. 34 E.

Chains	
	East on true line on South boundary of sec. 2. Var. 21° East.
14.00	Brook, 4 lks., flows S.
40.00	Set post and made mound of stone for $\frac{1}{4}$ sec. corner.
60.00	Brook, 4 lks., flows S.
80.00	Set post and raised stone mound for corner to secs. 1, 2, 11 and 12.
	Land, mountainous.
	Soil, 2nd rate.
	Good grass. Some good pine and fir timber.
	East on random between secs. 1 and 12. Var. 20° East.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
79.60	Intersect N. and S. line, 35 lks. S. of corner. South 89°25' West on true line.
39.80	Set post and made mound of stone for $\frac{1}{4}$ sec. corner.
79.60	To corner.
	Land, mountainous.
	Soil, 2nd rate.
	Excellent grass.
	North on random between secs. 1 and 2. Var. 19°30'E.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.57	Intersected North boundary at cor. South on true line.
40.57	Set post and made stone mound for $\frac{1}{4}$ sec. corner.
80.57	To corner.
	Table land.
	Soil, 2nd rate.
	Good grass. Some pine timber.
	North on random between secs. 2 and 3. Var. 20°E.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.50	Intersected North boundary, 47 lks. East of corner. S.00°20' East on true.