

Subdivisions of T. 1 N., R. 34 E.

| | |
|--------|---|
| Chains | |
| 40.50 | Set basalt stone, 18x14x10, for $\frac{1}{4}$ sec. corner. |
| 80.50 | To corner. |
| | Land, hilly. |
| | Soil, 2nd rate. |
| | Good grass. Some pine timber. |
| 5.50 | North between secs. 9 and 10. |
| 40.00 | Brook, 14 lks., flows E. |
| 40.00 | Set basalt stone, 18x14x4, for $\frac{1}{4}$ sec. corner. |
| 80.00 | Set basalt stone, 20x16x10, for corner to secs. 9, 10, 3 and 4. |
| | Land, hilly. |
| | Soil, 2nd rate. |
| | Good grass. Pine timber. |
| | East on random between secs. 3 and 10. |
| | Var. 22° East. |
| 40.00 | Set temporary $\frac{1}{4}$ sec. corner. |
| 80.00 | Intersected N. and S. line, 10 lks. South of cor. |
| | S.89°56'W. on true line. |
| 40.00 | Set post and made stone mound for $\frac{1}{4}$ sec. corner. |
| 80.00 | To corner. |
| | Land, hilly. |
| | Soil, 2nd rate. |
| | Good grass. Pine timber. |
| | North on random between secs, 3 and 4. |
| 40.00 | Set temporary $\frac{1}{4}$ sec. corner. |
| 80.48 | Intersected North boundary, 24 lks. East of corner. |
| | S.00°10'East on true line. |
| 40.48 | Set basalt stone, 14x10x10, for $\frac{1}{4}$ sec. corner. |
| 80.48 | To corner. |
| | Land, hilly. |
| | Soil, 2nd rate. |
| | Fine grass. Some good timber. |