

## West Boundary of T. 1 N., R. 35 E.

Chains	<p>Land, mountainous. 80 chs.            Soil, rocky, 4th rate.            Scattering pine timber on N. slopes.            Good bunch grass.</p>
40.00	<p>North between secs. 25 and 30.            Var. 19°30'E.</p> <p>Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor. marked <math>\frac{1}{4}</math> on W. face, from which</p> <p>A pine, 24 ins. in diam., bears S.45°E., 5 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>A pine, 16 ins. in diam., bears N.85°W., dist. 10 lks., marked <math>\frac{1}{4}</math> S B T.</p>
80.00	<p>Set a basalt stone, 18x10x8 ins., 12 ins. in the ground, for cor. to secs. 19, 24, 25 and 30 marked 2 notches on S. and 4 on N. edges, from which</p> <p>A pine, 16 ins. in diam., bears N.52°E., dist. 175 lks. marked T 1 N R 35 E S 19 B T.</p> <p>A fir, 10 ins. in diam., bears S.85°E., dist. 62 lks. marked S 30 B T.</p> <p>A fir, 12 ins. in diam., bears S.35°W., dist. 20 lks., marked S 25 B T.</p> <p>A pine, 18 ins. in diam., bears N.50°W., dist. 143 lks., marked R 34 E S 24 B T.</p> <p>Land, rolling.            Soil, rocky, 4th rate.            Timber, pine and fir. 80 chs.            Good bunch grass.</p>
20.00	<p>North between secs. 19 and 24.            Var. 20°30'E.</p> <p>Brink of canyon, heavy timber and underbrush.</p>
40.00	<p>Set a basalt stone, 10x8x7 ins., 6 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor. marked <math>\frac{1}{4}</math> on W. face, from which</p> <p>A pine, 20 ins. in diam., bears N.58°E., dist. 15 lks., marked <math>\frac{1}{4}</math> S B T.</p>