

Subdivisions of T. 1 N., R. 34 E.

Chains	
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect N. and S. line, 30 lks. S. of cor. to secs. 13, 14, 23 and 24. Thence I run S. $89^{\circ}47'W.$ on true line.
10.50	Canyon, course N.W.
40.00	Set basalt stone, 16x12x10 ins., 11 ins. in the ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor. Raised a mound of stone over it. Pits impracticable.
47.50	Gulch, course S.W.
80.00	To cor. to secs. 14, 15, 22 and 23. Land, mountainous, 40.00 chs.; and covered with good bunch grass. Soil, 3rd rate.
	North between secs. 14 and 15. Var. $24^{\circ} E.$
30.50	Gulch, course W.
40.00	Set basalt stone, 24x8x6 ins., 16 ins. in the ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor. Raised a mound of stone over it. Pits impracticable.
61.00	Lost Pin Creek, 5 lks. wide, course W.
80.00	Set basalt stone, 18x14x12 ins., 14 ins. in the ground, marked 4 notches on S. and 2 notches on E. edges, for cor. to secs. 10, 11, 14 and 15. Raised a mound of stone over it. Pits impracticable. Land, rough and mountainous. 80.00 chs. Soil, 2nd and 3rd rate.
	East on random between secs. 11 and 14. Var. $20^{\circ}15'E.$
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect N. and S. line at cor. of secs. 11, 12, 13 and 14. Thence I run W. on true line.
19.25	Creek, 5 lks. wide, course S. $80^{\circ}W.$
40.00	Set basalt stone, 12x12x10 ins., 8 ins. in the ground,