

Subdivisions of T. 1 N., R. 34 E.

Chains	
40.03	Set basalt stone, 12x9x7 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, raised mound of stone over it. Pits impracticable.
47.00	Foot of hill.
56.00	N. fork of McKay Creek, course N.W., water in holes.
69.50	Ledge of rock, leave creek bottom.
80.07	To cor. to secs. 27, 28, 33 and 34. Land, rough and mountainous. 80.07 chs. Some pine timber in creek bottom. Soil, 3rd rate.
North between secs. 27 and 28. Var. 22°E.	
22.75	North fork McKay Creek, course W.
25.00	Leave Creek bottom.
40.00	Set basalt stone, 12x8x7 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor., raised a mound of stone over it. Pits impracticable.
42.00	Top of mountain.
63.75	Branch of McKay Creek, course W.
80.00	Set basalt stone, 12x10x8 ins., 8 ins. in the ground, marked 2 notches on S., 3 notches on E. edges, for cor. to secs. 21, 22, 27 and 28. Raised mound of stone over it. Pits impracticable. Land, mountainous. 80.00 chs. Pine timber on Creeks. Soil, 3rd rate.
East on random between secs. 22 and 27. Var. 22°E.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.50	Intersect N. and S. line at cor. to secs. 22, 23, 26 and 27. Thence I run W. on true line.
9.50	Enter Creek bottom.
15.00	Branch McKay Creek, course S.W.