

Subdivisions of T. 1 N., R. 34 E.

Chains	S.89°47'W. on true line.
16.00	Summit ridge, course N.
34.25	Gulch, course N.E.
40.20	Set basalt stone, 12x9x6 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor., raised mound of stone over it. Pits impracticable.
45.00	Creek, course S.
80.40	To cor. to secs. 15, 16, 21 and 22. Land, mountainous and broken. 80.40 chs. Brush on N. hillsides. Soil, 3rd rate.
	North between secs. 15 and 16. Var. 19°25'E.
24.00	Top of ridge, course E. and W.
30.60	Canyon, course E.
40.00	Set basalt stone, 12x8x8 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor.
43.00	Top of ridge.
71.80	Branch McKay, 10 lks. wide, course S.W.
80.00	Set basalt stone, 16x10x8 ins., 11 ins. in the ground, marked 4 notches on S., 3 notches on E. edges, for cor. to secs. 9, 10, 15 and 16. Raised mound of stone around it. Pits impracticable. Land, mountainous, badly broken. 80 chs. Some pine and fir timber in canyons. Soil, rocky and 3rd rate.
	East on random between secs. 10 and 15. Var. 21°45'E.
40.00	Temporary $\frac{1}{4}$ sec. cor.
79.84	Intersect N. and S. line, 48 lks. N. of cor. to secs. 10, 11, 14 and 15. Thence I run N.89°39'W. on true line.
5.00	Stream, 5 lks. wide, course S.
30.00	Summit of mountain.