

Subdivisions of T. 1 N., R. 34 E.

Chains	<p>marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor., from which</p> <p>A pine, 20 ins. diam., bears S.20°W., dist. 36 lks., marked $\frac{1}{4}$ S B T.</p> <p>A pine, 24 ins. diam., bears N.60°W., dist. 61 lks., marked $\frac{1}{4}$ S B T.</p> <p>Raised mound of stone over it. Pits impracticable.</p> <p>60.00 Summit of ridge.</p> <p>80.25 To cors. of secs. 3, 4, 9 and 10.</p> <p>Timber in W.$\frac{1}{2}$ of line.</p> <p>Land, mountainous. 80.25 chs.</p> <p>Soil, 3rd rate.</p>
	<p>North on random between secs. 3 and 4.</p> <p style="text-align: center;">Var. 21°E.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor.</p> <p>80.00 Intersect T. line at cor. to secs. 3, 4, 33 and 34.</p> <p>Thence I run S. on true line.</p> <p>40.00 Set post, 3ft. long, 3 ins. sq., 2 ft. in ground, marked $\frac{1}{4}$ S on W. face, for $\frac{1}{4}$ sec. cor., from which</p> <p>A pine, 5 ins. diam., bears S.15°W., dist. 12 lks., marked $\frac{1}{4}$ S B T.</p> <p>A pine, 5 ins. diam., bears N.35°E., dist. 70 lks., marked $\frac{1}{4}$ S B T.</p> <p>80.00 To cor. to secs. 3, 4, 9 and 10.</p> <p>Land, rolling.</p> <p>Some scattering pine. Good bunch grass.</p> <p>Soil, 3rd rate.</p>
	<p>From cor. to secs. 32 and 33 on S. bdy. of Township I run North between secs. 32 and 33.</p> <p style="text-align: center;">Var. 21°E.</p> <p>5.00 Bottom of canyon, course N.W.</p> <p>26.00 Top of ridge, course E. and W.</p> <p>37.00 Canyon, course W.</p> <p>40.00 Set basalt stone, 10x8x7 ins., 7 ins. in the ground, marked $\frac{1}{4}$ on W. face, for $\frac{1}{4}$ sec. cor. Raised mound of stone</p>