

Subdivisions of T. 1 N., R. 34 E.

| | |
|--------|--|
| Chains | East on random between secs. 20 and 29. Var. 19°E. |
| 40.00 | Set temporary $\frac{1}{4}$ sec. cor. |
| 80.35 | Intersect N. and S. line, 5 lks. N. of cor. to secs. 20, 21, 28 and 29. Thence I run N.89°58'W. on true line. |
| 9.00 | Trail on summit, course S. |
| 28.00 | Spring branch in Gulch, course S. |
| 40.17 | Set basalt stone, 16x10x8 ins., 11 ins. in the ground, marked $\frac{1}{4}$ on N. face, for $\frac{1}{4}$ sec. cor. Raised a mound of stone over it. Pits impracticable. |
| 45.75 | Gulch, course S. |
| 76.50 | Gulch, course S. |
| 80.35 | To cor. to secs. 19, 20, 29 and 30. Land, rough and mountainous. 80.35 chs. Soil, 4th rate. |
| | West on random between secs. 19 and 30. Var. 19°E. |
| 40.00 | Set temporary $\frac{1}{4}$ sec. cor. |
| 82.56 | Intersect Tp. bdy, 1.39 lks. N. of cor., to secs. 24, and 25. Thence I run N.89°02'E. on true line. |
| 16.00 | Leave table land; descend. |
| 42.50 | Set a stone, 18x10x10 ins., 12 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face. Raised a stone mound over it. Pits impracticable. |
| 43.25 | Canyon, course S. |
| 61.00 | Summit. |
| 70.00 | Gulch, course S. |
| 82.56 | To cor. to secs. 19, 20, 29 and 30. Land, mountainous. 66.56 chs. Soil, 3rd rate. Good grass. August 9, 1887. |