

Subdivisions of T. 1 N., R. 34 E

Chains	North between secs. 19 and 20. Var. 19°E.
12.00	Ledge of rock.
17.00	Summit of mountain.
25.00	Descend into timber.
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, marked $\frac{1}{4}$ S on W. face, for $\frac{1}{4}$ sec. cor., from which A pine, 18 ins. in diam., bears S.55°W., dist. 15 lks., marked $\frac{1}{4}$ S B T; also A pine, 10 ins. in diam., bears S.82°E., dist. 63 lks., marked $\frac{1}{4}$ S B T.
48.00	Wagon Road, course W.
50.00	Ravine, course E.
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in the ground, for cor. to secs. 17, 18, 19 and 20, marked T 1 N S 17 on N.E., R 34 E S 20 on S.E., S 19 on S.W., S 18 on N.W. faces with 5 notches on E. edge and 3 notches on S. edge, from which A pine, 20 ins. in diam., bears N.45°E., dist. 50 lks., marked S 17 T 1 N B T; also A pine, 24 ins. in diam., bears N.10°W., dist. 83 lks., marked S 18 B T; also A pine, 10 ins. in diam., bears S.32°W., dist. 150 lks., marked S 19 B T; also A pine, 20 ins. in diam., bears S.5°E., dist. 57 lks., marked S 20 R 34 E B T.
	Table land.
	Heavy pine timber. 55 chs.
	Soil, 2nd rate.
	East on random between secs. 17 and 20. Var. 19°E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.58	Intersect N. and S. lines, 40 lks. N. of cor. to secs. 16, 17, 20 and 21. Thence I run