

0*

Subdivisions and Allotments of T. 1 N., R. 34 E.

Chains	Sec. 6
	<p>stone, $5\frac{1}{2}$ ft. dist., and mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base alongside.</p> <p>I run</p> <p>N. $0^{\circ}54'E.$ on true line between secs. 5 and 6.</p> <p style="text-align: center;">Var. $20^{\circ}E.$</p>
8.00	Pendleton and LaGrande Wagon road, course N.W.
10.00	<p>Set basalt stone, $11 \times 10 \times 7$ ins., 7 ins. in the ground, for $\frac{1}{32}$ sec. corner marked $\frac{1}{32}$ on W. face. Dug pits, $18 \times 18 \times 12$ ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p style="text-align: center;">Var. $18^{\circ}30'E.$</p>
30.00	<p>Set basalt stone, $9 \times 8 \times 7$ ins., 6 ins. in the ground, for $\frac{1}{16}$ sec. corner marked $\frac{1}{16}$ on W. face, and raised mound of stone over it. Pits impracticable. This corner stands on N.E. slope.</p> <p>Land, rolling and inclined to the North.</p> <p>Soil, 1st rate and rocky.</p> <p>Good grass.</p>
	<p>From the $\frac{1}{16}$ sec. corner, 10 chs. North of $\frac{1}{4}$ sec. corner between secs. 5 and 6.</p> <p>I run</p> <p>West on true line in sec. 6.</p> <p style="text-align: center;">Var. $18\frac{1}{2}^{\circ}$ East.</p>
3.50	Pendleton and LaGrande wagon road, course N.W.
20.00	<p>Set basalt stone, $10 \times 8 \times 7$ ins., 6 ins. in the ground, for $\frac{1}{16}$ sec. corner marked $\frac{1}{16}$ on N. face, and raised a mound of stone over it. Pits impracticable.</p> <p>Land, rolling and inclined to North.</p> <p>Soil, 1st rate and rocky.</p> <p>Good grass.</p>
	<p>From the $\frac{1}{16}$ sec. corner, 10 chains N., and 20 chains W. of $\frac{1}{4}$ sec. corner between secs. 5 and 6.</p> <p>I run</p>