

Subdivisions and Allotments of T. 1 N., R. 34 E.

Chains	Sec. 8
	<p>marked with 4 notches on S. and 5 notches on E. edges, mound of stone over it.</p> <p>I run</p> <p>East on a true line between secs. 8 and 17.</p> <p style="text-align: center;">Var. 18°45'E.</p>
3.50	Gulch, course N.
10.02	<p>Set a post, 3 ft. long, 3 ins. square, 24 ins. in the ground, for 1/32 sec. corner marked 1/32 S on N. face, from which</p> <p style="padding-left: 40px;">A pine, 8 ins. diam., bears S.45°W., 163 lks. dist., marked 1/32 S B T.</p> <p style="padding-left: 40px;">A pine, 12 ins. diam., bears S.25°W., 145 lks. dist., marked 1/32 S B T.</p>
20.04	<p>Set basalt stone, 10x9x8 ins., 6 ins. in the ground, for 1/32 sec. cor. marked 1/32 on W. and 1/16 on E., and D R on N. edges, raised a mound of stone over it.</p> <p>Pits impracticable.</p>
40.08	<p>To the 1/4 sec. corner, which is basalt stone, 20x12x3 ins., 15 ins. in the ground, marked 1/4 on N. face, from which</p> <p style="padding-left: 40px;">A pine, 10 ins. diam., bears N.83°E., 65 lks. dist., marked 1/4 S B T.</p> <p style="padding-left: 40px;">A pine, 12 ins. diam., bears S.50°E., 84 lks. dist., marked 1/4 S B T.</p>
50.00	<p>Set basalt stone, 11x7x6 ins., 6 ins. in the ground, marked 1/32&D R on N. face, from which</p> <p style="padding-left: 40px;">A pine, 30 ins. diam., bears S.10°W., 10 lks. dist., marked 1/32 S B T.</p> <p style="padding-left: 40px;">A pine, 20 ins. diam., bears N.75°E., 20 lks. dist., marked 1/32 S B T.</p> <p>Land, gently rolling.</p> <p>Soil, 2nd rate.</p> <p>Timber, pine.</p>
	<p>From the 1/4 sec. corner between secs. 8 and 17.</p> <p>I run</p> <p>North on true line in the center of sec. 8.</p>