

## Subdivisional Lines, T. 1 N., R. 35 E.

Chains	
	<p>Knowing that I will strike the bdy. of Umatilla Reservation in less than 80 chains, I run East on true line bet. secs. 27 &amp; 34. Var. 19°40' East.</p>
39.50	Spring branch 6 lks. run S.
40.00	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for <math>\frac{1}{4}</math> S. corner, marked <math>\frac{1}{4}</math>S on N. face, from which A Pine 10 ins. in diam. bears N63°W.30 lks. dist., marked <math>\frac{1}{4}</math> S. B. T. A Pine, 10 ins. in diam. bears S20°W40 lks. dist., marked <math>\frac{1}{4}</math> S. B. T. Ascend gradual slope.</p>
71.00	<p>Intersect U.R. bdy. 6.25 chs. S.20°W. of 49th mile cor. and set post 4 ft. long, 4 ins. square, 24 ins. in the ground, marked U.R.C.C. on W.; T.1N.S27 on N. and R.35E. S.34 on S. faces, from which A Pine 18 ins. diam. bears S10°E.70 lks. dist., marked T.1 N S34 U.R.C.C.B.T. A Pine 30 ins. diam. bears N32°E.215 lks. dist., marked R35E.S27 U.R.C.C.B.T.</p>
80.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for corner to secs. 26, 27, 34 &amp; 35, marked T1N S26 on N.E.; R35E S35 on S.E.; S34 on S.W. and S27 on N.W. faces with 1 notch on S and 2 notches on E. edges; raised mound of stone around it. Pits impracticable. Land, rolling. Soil, 1st rate. Timber: Pine &amp; Fir, scattering. Bunch grass.</p>
	<p>North bet. secs. 26 &amp; 27. Var. 20° East.</p>
12.00	Ravine West.
24.75	<p>Intersect U.R. bdy. 20.08 chs. N20°E. 49th mile cor. Set basalt stone 8 x 10 x 20 ins., 15 ins. in the ground for closing cor. to Secs. 26 &amp; 27, marked U.R.C.C. on</p>