

Subdivisional lines, T 1 N.R. 35 E.

| Chains | | |
|--------|--|-------|
| | North between Secs. 22 & 23. | |
| | Var. 20° East | |
| 11.30 | Deep ravine N.W. | -50 |
| 24.50 | A pine, 36 ins. diam. | |
| 40.00 | Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ S on W. face, from which A fir 10 ins. diam. bears N60°E. 43 lks. dist., marked $\frac{1}{4}$ S. B. T. A fir 10 ins. diam. bears N30°W 80 lks. dist., marked $\frac{1}{4}$ S. B. T. | |
| | Begin descent. | |
| 66.25 | Creek, 15 lks. Course N.W. | -100 |
| | Ascend. | |
| 80.00 | Set basalt stone 16 x 10 x 8 ins., 12 ins. in the ground for cor. to secs. 14, 15, 22 & 23, marked with 3 notches on S and 2 notches on E edges, and raised mound of stone over it. Pits impracticable. | +500 |
| | Land, rough and mountainous. 80 chs. | |
| | Soil, rocky, 4th rate. | |
| | Timber: Fir, pine and tamarack in canons, also underbrush same. | |
| | East on true line bet. secs. 14 & 23. | |
| | Var. 19° East. | |
| | Ascend steep hillside. | |
| 12.50 | Top mountain. | +1200 |
| 37.50 | Canon S.W. | - 100 |
| 40.00 | Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ S. corner, marked $\frac{1}{4}$ S. on N face, from which A Fir 10 ins. diam. bears N77°W 62 lks. dist., marked $\frac{1}{4}$ S. B. T. A Fir 12 ins. diam. bears S48°E 65 lks. dist., marked $\frac{1}{4}$ S. B. T. | |
| 45.95 | Intersect U.R. bdy. 4.13 chs. N20°E. of 47th Mile corner and set post 4 ft. long, 4 ins. square, 24 ins. in the | |