

## Subdivisional lines, T. 1 N.R. 35 E.

| Chains |                                                                                                                                                                                                                                                                                                                                                               |       |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|
|        | <p>ground for Closing corner to secs. 14 &amp; 23, marked U.R.C.C. on W. face; T1 N S14 on N and R35E S23 on S faces; raised mound of stone around post. Pits impracticable.</p> <p>Land, rough and mountainous, 40.95 chs. Soil, poor, 4th rate. Grass good. Timber: Pine, Fir &amp; Tamarack.</p> <p style="text-align: right;">June 20th, 1887.</p>        |       |
|        | <hr/>                                                                                                                                                                                                                                                                                                                                                         |       |
|        | <p>North bet. secs. 14 &amp; 15.</p> <p style="text-align: right;">Var. 19° East.</p>                                                                                                                                                                                                                                                                         |       |
| 10.00  | Summit of ridge.                                                                                                                                                                                                                                                                                                                                              | +300  |
| 39.00  | Creek, 2 lks. Course W. in canon.                                                                                                                                                                                                                                                                                                                             | -1200 |
| 40.00  | <p>Set basalt stone 16 x 16 x 10 ins., 12 ins. in the ground for <math>\frac{1}{4}</math> sec. corner, marked <math>\frac{1}{4}</math> on W. face, from which</p> <p>A Fir 10 ins. diam. bears S2°E. 100 lks. dist., marked <math>\frac{1}{4}</math> S.B.T.</p> <p>A Pine 36 ins. diam. bears S70W. 43 lks. dist., marked <math>\frac{1}{4}</math> S.B.T.</p> |       |
| 72.50  | Summit mountain W.                                                                                                                                                                                                                                                                                                                                            | +1200 |
| 80.00  | <p>Set basalt stone 12 x 10 x 10 ins., 8 ins. in the ground for cor. to secs. 10, 11, 14 &amp; 15, marked with 4 notches on S. and 2 notches on E. edges and raised mound of stone over it. Pits impracticable.</p> <p>Land, rough and mountainous 80.00 chs.</p> <p>Soil, 2nd rate.</p> <p>Timber: Fir and Pine in canons.</p>                               |       |
|        | <hr/>                                                                                                                                                                                                                                                                                                                                                         |       |
|        | <p>East on true line between secs. 11 &amp; 14.</p> <p style="text-align: right;">Var. 19° East.</p>                                                                                                                                                                                                                                                          |       |
| 4.00   | Ravine N.                                                                                                                                                                                                                                                                                                                                                     | -150  |
| 22.50  | Summit Hill N                                                                                                                                                                                                                                                                                                                                                 | +200  |
| 31.50  | Ravine N.W.                                                                                                                                                                                                                                                                                                                                                   | -300  |
| 40.00  | <p>Set basalt stone 12x12x10 ins., 8 ins. in the ground for <math>\frac{1}{4}</math> S. cor., marked <math>\frac{1}{4}</math> on N. face and raised mound of stone over it. Pits impracticable.</p>                                                                                                                                                           | +300  |