

## Subdivisional lines, T. 1 N.R. 35 E.

Chains		
45.00	Summit N.W. Descend.	+400
75.50	Intersect U.R. bdy. 938 lks. N20°E. of 46th Mile cor. and set stone 18 x 10 x 6 ins., 12 ins. in the ground for Closing cor. to secs. 11 & 14, marked U.R.C.C. on W.face and raised mound of stone over it. Pits impracticable. Land, mountainous, rocky. 75.50 chs. Soil, 1st rate on N.W. hillsides; otherwise, poor. Grass, good.	-200
June 20, 1887.		
North bet. secs. 10 & 11.		
Var. 19° East.		
12.00	Canyon and creek, 12 lks. Course W.	-600
40.00	Set basalt stone 12 x 17 x 6 ins., 10 ins. in the ground for $\frac{1}{4}$ S.cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone over it. Pits impracticable.	-400
Ascend.		
50.00	Summit ridge W.	+800
80.00	Set basalt stone 18 x 10 x 10 ins., 12 ins. in the ground for corner to secs. 2,3,10 & 11, marked with 5 notches on S and 2 notches on E edges and raised mound of stone over it. Pits impracticable.	
Land, mountainous 80.00 chs.		
Soil, 2nd rate and rocky.		
Timber: Pine & fir on N. hillsides.		
Grass, good.		
East on true line bet. secs. 2 & 11.		
Var. 19°45' East.		
5.00	Gulch N.	-150
17.50	Summit.Spur or sharp ridge	+100
29.75	Gulch N.	-200
32.50	Gulch N.	-100
40.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground	