

Subdivisional Lines, T. 1 N., R. 35 E.

Chains		
	<p>marked T.1 N.S.22 B.T.</p> <p>A Pine 24 ins. in diam. bears S.35° E.72 lks. dist., marked R35 E.S.27 B.T.</p> <p>A Pine 18 ins. in diam. bears S.45°W.58 lks. dist., marked T.1 N.R. 35 E.S28 B.T.</p> <p>No other trees in limits, I raised mound of stone along- side.</p> <p>Land, rolling. Soil, good. Timber, pine, fir & tamarack. Considerable underbrush.</p>	
	<hr/>	
	<p>East on random bet. Secs. 22 & 27.</p> <p style="text-align: right;">Var. 18° East.</p>	
40.00	Set temporary $\frac{1}{4}$ Sec. cor. and at	
80.20	Intersect E. bdy. at cor. to secs. 22,23,26 & 27.	
	Thence, east	
	<p>West on true line</p> <p style="text-align: right;">Var. 20° East.</p>	
40.10	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$S on N face, from which</p> <p>A Fir 8 ins. in diam. bears N.25°W.37 lks. dist., marked $\frac{1}{4}$ S. B. T.</p> <p>A Fir 20 ins. in diam. bears S.50°E.27 lks. dist., marked $\frac{1}{4}$S.B.T.</p>	
80.20	<p>Cor. to Secs. 21, 22, 27 & 28.</p> <p>Land, rolling. Timber: Pine and fir scattering.</p> <p>Soil, 1st rate. Grass, good. Some underbrush.</p> <p style="text-align: right;">June 21, 1887.</p>	
	<hr/>	
	<p>North bet. Secs. 21 and 22.</p> <p style="text-align: right;">Va. 18° East.</p>	
16.50	Canon N.W.	-100
25.00	Top ridge N.W.	+100
30.00	Canon N.W.	-200
40.00	<p>Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ on W. face; raised mound of stone over it. Pits impracticable.</p>	