

Subdivisional lines, T. 1 N., R. 35 E.

Chains		
50.00	Summit hill. Descend.	+500
80.00	Set basalt stone 14 x 10 x 6 ins., 9 ins. in the ground for cor. to secs. 15, 16, 21 & 22, marked with 3 notches on S. and E. edges; raised mound of stone over it. Pits impracticable. Land, rough and mountainous 80.00 chs. Soil, 4th rate and rocky. Scattering pine and fir. Grass, good. June 21, 1887.	
	East on random bet. Secs. 15 & 22. Var. 18° East.	
40.00	Set temporary $\frac{1}{4}$ S. cor. and at	
80.24	Intersect E. bdy. at cor. to secs. 14, 15, 22 & 23. Thence West on true line Var. 19° East.	
16.00	Creek in canon 16 links, runs N. Ascend, steep hill side.	-1200
40.12	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ S. cor., marked $\frac{1}{4}$ on N. face; raised mound of stone over it. Pits impracticable.	
60.00	Summit ridge N.	+800
80.24	Cor. to secs. 15, 16, 21 & 22. Land, rough and mountainous 80.24 chs. Soil, 2nd rate. Bunch grass. Timber: Pine & fir in canons.	
	North bet. Sections 15 & 16. Var. 18° East.	
	Descend.	
27.00	Creek bottom and timber.	-600
40.00	Set stone 18 x 8 x 8 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W. face, from which	+400