

Subdivisional lines, T. 1 N., R. 35 E.

Chains		
	North bet. secs. 3 & 4. Var. 19° East.	
21.00	Gulch, W.	-300
27.50	Brow of hill.	+100
40.00	Set basalt stone 10 x 10 x 10 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face and raised mound of stone over it.	
40.75	Gulch W.	-100
55.00	Summit ridge W.	+50
62.30	Creek N.W.	-100
80.40	Intersect Tp. line 340 lks E. of cor. to secs. 33 & 34, Tp. 2 N.R. 35 E. and set stone 16 x 10 x 5 ins., 10 ins. in the ground for Closing cor. to Secs. 3 & 4, marked C.C. on S face with 3 notches on E and W edges; raised mound of stone over it. Pits impracticable. Land, rough and mountainous 80.40 chs. Soil, 2nd rate. Grass, good. Timber, scattering Pine & Fir. June 22, 1887.	
	From cor. to Secs. 32 & 33 on S. bdy of Tp., I run North bet. secs. 32 & 33. Var. 19° East.	
	Descend gradual slope.	
40.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ S on W. face, from which A Pine 6 ins. in diam. brs. S 10° East 29 lks. dist., marked $\frac{1}{4}$ S. B. T. A Tamarac, 10 ins. in diam. brs. N.73° W. 72 lks. dist. marked $\frac{1}{4}$ S. B. T.	
78.00	Old Stage Road N.W. and S.E.	
80.00	Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for cor. to secs. 28, 29, 32 & 33, marked with 1 notch on S. and 4 notches on East edges, from which A Pine 10 ins. in diam. bears N.44° E., 18 lks. dist., marked T.1 N.S.28 B.T. A Pine 12 ins. in diam. bears S.67°E., 22 lks. dist., marked R.35 E.S.33 B.T. A Pine 10 ins. in diam. bears S.55° W. 11 lks. dist., marked T.1 N.S.32 B.T.	