

Subdivisions, T. 1 N.; R. 35 E.

Chains		
	North bet. secs. 19 & 20. Var. $20\frac{1}{2}^{\circ}$ East.	
20.10	Canons W.	-100
40.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S on W. face, from which A fir 12 ins. in diam. bears N.80°E.41 lks. dist., marked $\frac{1}{4}$ S. B. T. A fir 10 ins. in diam. bears N.19°W.78 lks. dist., marked $\frac{1}{4}$ S. B. T.	
72.50	Spring branch E.	-100
80.00	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to secs. 17, 18, 19 & 20, marked T.1,N.S.17 on N.E.; R35 E. S.20 on S.E.; S19 on S.W. and S18 on N.W. faces, with 3 notches on S. and 5 notches on E. edges, from which A fir, 18 ins. in diam. bears N25°E.17 lks. dist., marked T1N S 17 B. T. A fir 6 ins. in diam. bears S.30° E. 25 lks. dist., marked R35 E S20 B. T. A fir 10 ins. diam. bears S.10° W.38 lks. dist., marked T.1 N.S. 19 B. T. A fir 12 ins. in diam. bears N.20° W. 10 lks. dist., marked R35 E S.18 B. T.	
	Land, rolling. Soil, 2nd rate, rocky.	
	Timber, pine and underbrush.	
	June 25, 1887.	
	East on random bet. secs. 17 & 20.	
	Var. 19° East.	
40.00	Set temporary $\frac{1}{4}$ S. cor. and at	
80.30	Intersect E. bdy. at cor. to secs. 16, 17, 20 & 21,	
	Thence	
	West on true line.	
	Var. same.	
15.37	Pendleton and La Grande wagon road N & S.	
40.15	Set basalt stone 12 x 10 x 10 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, from which	