

Subdivisional Lines, T. 1 N., R. 35 E.

Chains	North bet. secs. 17 & 18.	
		Var. $20\frac{1}{2}^{\circ}$ East.
	Through scattering pine timber.	
25.00	Head of canyon W.	-50
40.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ S on W. face, from which A tamarack, 14 ins. in diam. bears $N.85^{\circ} W. 28$ lks. dist. marked $\frac{1}{4}$ S B T. A fir, 16 ins. in diam. bears $S45^{\circ} E.30$ lks. dist., marked $\frac{1}{4}$ S B T.	
	Ascend.	
55.00	Top of hill.	+400
	Descend.	
68.00	Creek in canyon.	-400
80.00	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for cor, to secs. 7, 8, 17 and 18 marked with 4 notches on S. and 5 notches on E. edges and raised mound of stone over it. Pits impracticable. Land, somewhat broken. Soil, generally good. Timber, scattering pine. Bunch grass, fine.	
<hr/>		
	East on random bet. secs. 8 & 17.	
		Var. $19^{\circ} 30'$ East.
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.90	Intersect N & S line at cor. to secs. 8, 9, 16 and 17. Thence	
	West on true line	
		Variation, same.
	Ascend.	
10.00	Top of hill or ridge S.	+100
25.00	Canyon S.W.	-100
	Ascend.	
30.00	Enter small prairie.	
39.95	Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face and raised mound of stone over it. Pits impracticable.	