

Subdivisional lines, T. 1 N., R. 35 E.

| | | |
|--------|---|------|
| Chains | Soil, 4th rate and rocky. Timber in canons pine and fir. Fine bunch grass. June 27th, 1887. | |
| | North bet. secs. 7 and 8. Var. 19 $\frac{1}{2}$ East. | |
| 15.00 | Begin ascent. | |
| 30.00 | Top mountain above sec. cor. Descend. | +800 |
| 40.00 | Set basalt stone 12 x 8 x 8 ins., 10 ins. in the ground for $\frac{1}{4}$ S. cor., marked $\frac{1}{4}$ on W. face, from which A fir 12 ins. in diam. bears N.50° W. 23 lks. dist., marked $\frac{1}{4}$ S. B. T. A fir 10 ins. in diam. bears S.25° E. 50 lks. dist., marked $\frac{1}{4}$ S. B. T. Continue descent. | |
| 46.50 | Head water of N. fork of McKay Creek 5 lks., runs S.W. Ascend. | -800 |
| 73.50 | Top of mountain. Descend. | +800 |
| 78.00 | Canon S.W. Ascend steep hill covered with brush fir and pine. | -100 |
| 80.00 | Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to secs. 5, 6, 7 and 8 marked T1N S5 on N.E.; R35E S8 on S.E.; S7 on S.W. and S.6 on N.W. faces with 5 notches on S and E edges, from which A pine 8 ins. in diam. bears N.62° E. 130 lks. dist., marked T1 N S5 B.T. A pine 16 ins. in diam. bears S.15° E. 40 lks. dist., marked R35 E S8 B.T. A fir 14 ins. in diam. bears S.35° W. 35 lks. dist., marked T.1 N.S.7 B.T. A fir 18 ins. in diam. bears N75° W 70 lks dist., marked R.35 E. S.6 B.T. Land, rough and mountainous 80.00 chains, badly broken by small ridges and canons. Soil, 2nd rate, unfit for any- thing but pasture. Fine bunch grass. Timber, pine and fir in canons and on S. hill sides. | |