

## Subdivisions of T.1 N., R. 35 E.

Chains	
18.50	Top of sharp N.W. point - 250' ft. above creek - descend W. face.
23.67	Spring brook - course N.E. - 200 ft. Ascend steep.
39.93½	Set a basalt stone 18 x 10 x 6 ins. on rock in mound of stone, marked ¼ on N. face; and raised a mound of stone 2 ft. base, and 1½ ft. high, N. of cor. Pits impracticable.  This cor. is on summit of a ridge 300 ft. above creek, bears N.W. and S.E.  Descend over very broken land.
79.87	The cor. to secs. 11, 12, 13 and 14.  Land, mountainous hills. Soil, sandy, gravelly loam, 3rd and 4th rate.  Timber, heavy young pine, fir, tamarac and spruce.  Mountainous lands, 79.87 chs.
<hr/> The closing corner to secs. 11 and 14 on U. I. R. line being in sight, I run for it S.88° 19' W. on true line bet. secs. 11 and 14. Descending gradually.	
1.00	Leave brush.
3.97	Intersect U.I.R. line at closing corner to secs. 11 and 14, which is a stone 18 x 10 x 6 ins., in a mound of stone, marked U.R.C.C. on N. face.  Land, rolling. Soil, sandy loam - 3rd rate.  No timber, very little brush.  Mountainous lands 3.97 chs.
<hr/> The closing corner to secs. 11 and 12 on the U.I.R. line being within sight, I set a flag thereon and run to it N. 2°26' W. on true line bet. secs. 11 and 12. Descend through undergrowth.	
1.71	Bottom of ravine, course N.E. Ascend.
3.50	Leave brush.
11.50	Intersect U.I.R. line at closing corner to secs. 11 and 12.